

TEC Minneapolis Blower Door Test with DG-1000 Manometer

| BLOWER DOOR FIELD GUIDE | |
|---|---|
| <p>1-Point Depressurization Model 3 Fan, 115V</p> | |
| <p>1. TURN OFF Vented Combustion Appliances</p> | <p>5. SETUP Blower Door Frame and Panel</p> |
| <p>Fireplaces & Woodstoves: Cold, no coals, close dampers, cover ashes with wet paper.</p> <p>TURN OFF all Vented Combustion Appliances</p> <p>Water Heater Turn to PILOT or OFF (<i>car keys</i>)</p> <p>All Boilers Turn off <u>at unit</u> or elec panel !! <i>> Make sure water heater won't start!</i></p> <p>Furnace Can use T-stat, check air filter</p> <p>Clothes Dryer Turn off: check Filter & Outlet</p> <p>Exhaust Fans Turn off all vented exhaust fans</p> | <p>Exterior Door of Conditioned Space Green Hose to <u>Outside</u>, 5' to the Side</p> <p>Red Hose to small brass port at top of fan</p> <p>Install Fan, Close all Rings to prepare for Baseline</p> <p>Power Supply to Fan (check power)</p> |
| <p>2. CLOSE up the HOUSE as in Winter</p> | <p>6. DG-1000 MANOMETER - use Tubing Assistant</p> |
| <p>Exterior Windows and Doors</p> <p>Garage, Basement, Crawl space</p> <p>Attic Accesses, including kneewall hatches</p> | <p>7. SET BASELINE - min 30 sec</p> |
| <p>3. OPEN ALL INTERIOR DOORS</p> | <p>8. CONFIG: CHOOSE FAN RING (CFM50)</p> |
| <p>Is there a Drop Ceiling? Remove panel & inspect. Consider doing a Pressurization test.</p> | <p>Open: 6,100 - 2,435 Switch to A-Ring at 2,500</p> <p>Ring A: 2,800 - 915 Switch to B-Ring @ 1,000</p> <p>Ring B: 1,100 - 300 Switch to C-Ring @ 315</p> <p>Ring C: 330 - 85</p> |
| <p>4. SET UP FOR ATTIC ZONE PRESSURE TESTS</p> | <p>9. RUN FAN 3-5 min for pressures to equalize</p> |
| <p>Attic Bypass: basement door closed, then open. <i>> Want Attic Zone Pressure to hold, not decrease.</i></p> | <p><i>> Watch fireplace and wood stove for ashes</i></p> |
| <p>5. SETUP Blower Door Frame and Panel</p> | <p>10. CHANGE a RING? First change CONFIG, then ring.</p> |
| <p>Exterior Door of Conditioned Space Green Hose to <u>Outside</u>, 5' to the Side</p> <p>Red Hose to small brass port at top of fan</p> <p>Install Fan, Close all Rings to prepare for Baseline</p> <p>Power Supply to Fan (check power)</p> | <p>If "LO" Add Ring (house@50pa, fan slow < 25pa)</p> <p>If CR50 Remove Ring (fan at full speed) (consider another fan?)</p> |
| <p>6. DG-1000 MANOMETER - use Tubing Assistant</p> | <p>11. Use TIME AVG when windy, or to photograph</p> |
| <p>7. SET BASELINE - min 30 sec</p> | <p>12. NOTE how the house is setup for each test. (e.g. Basement or CAZ doors open or closed)</p> |
| <p>8. CONFIG: CHOOSE FAN RING (CFM50)</p> | |
| <p>9. RUN FAN 3-5 min for pressures to equalize</p> | |
| <p>10. CHANGE a RING? First change CONFIG, then ring.</p> | |
| <p>11. Use TIME AVG when windy, or to photograph</p> | |
| <p>12. NOTE how the house is setup for each test. (e.g. Basement or CAZ doors open or closed)</p> | |

| | |
|--|--|
| DG-700 MANOMETER SETUP | |
| 1-Point Depressurization with Manometer INSIDE | Depressurization Test with Manometer OUTSIDE |
| <p>Green Hose: Left/REF to Outside Red Hose: Right/Input to Fan Press: ON, Mode, Mode (PR/FL@50) Press: Baseine, Start (wait 30 sec), Enter. see "ADJ" Turn Rheostat to 50 PA (House WRT Outside)</p> | <p>Green Hose: Left/Input to Indoors Red Hose: Right/Input to Fan Clear Hose: Right/Ref to Interior</p> |
| Using the CRUISE feature | PRESSURIZATION Test: Manometer INSIDE |
| <p>Rheostat at Lowest Setting Press: Begin Cruise. Shows the target @50PA target Press: Start Fan. Automatically increases to 50PA Press: Stop Fan to pause. Press again to cancel.</p> | <p>Turn Fan around to blow air IN Green Hose: Left/REF to Outside Red Hose: Right/Input to Fan Clear Hose: Right/Ref to Outside</p> |